

National & International Award Winner



An ISO 9001:2008 Company


Why **EVERLAST**?

It has its own advantages over traditional materials:


- Waterproof, Weatherproof & Non-Corrosive
- Burglarproof
- ZERO SCRAP VALUE
- High strength to weight ratio
- Light weight - ease of handling
- Various options of decorative surface designs & granite finishes
- Life span of 30+ years
- Can be designed to take load from 1.5 ton to 40 ton
- Load designation conforming to IS 1726:1991 are 2.5, 10, 20 & 35 ton & EN-124 are 1.5, 12.5, 25 & 40 ton
- Logo embossing options available
- Approved by Government & Semi Government agencies like MCGM, MES (Navy) & MTNL

Approved by **MCGM**

GRP/FRP/Composite Manhole Covers & Gratings



- Zero Scrap Value
- Weatherproof
- Heavy Duty
- Light Weight
- Decorative
- Burglarproof



Manhole Covers & Frames, Gratings confirming to EN124:1994 and IS1726:1991 are available in following clear opening sizes(in mm) for load capacities from 1.5 Ton to 40 Ton.:

Circular	Dia 530	Dia 560	Dia 600	Dia 750	Dia 900
Square	300 x 300	450 x 450	600 x 900	900 x 900	1000 x 1000
Rectangular	450 x 600	450 x 900	450 x 900	900 x 1200	
Gratings with Frame	450 x 450	500 x 600	600 x 600	600 x 1200	
Gratings without Frame	295 x 525	375 x 500	450 x 450	500 x 550	

Dia 600mm Water Tight Underground Tank Covers available for load capacities from 5 Ton to 40 Ton. Overhead Tank Covers are also available in Dia 450mm, Dia 530mm and Dia 600mm.

Shade Card*

Note: Can be designed and manufactured as per your requirements.



* Actual colours may vary from visual representation

Size Selection & Installation

Size Selection: Clear opening of the frame should not be smaller than that of chamber.

Installation Procedure

- Prepare concrete bed considering height of frame
- Frame should be embedded in 300 x 200 mm of minimum M-20 grade concrete
- Make sure that top level of frame should match with the road

